



- CHIMNEY TO EXTEND MIN 24" ABOVE ANY ROOF EAVES OR HORIZONTAL
  - ROOFING MATERIAL (SEE ROOF PLAN)
  - G. 1. GUTTER ON 2" X 8" FASCIA C/D DOWNSPUTS (SEE ROOF PLAN)
  - CEDAR SHINGLE SIDING INSTALL PER MANUF. SPECS
  - 1/4" X CEDAR CORNER BOARDS
  - 2" X 10 R/S TRIM ED. W/ 3/8" GALV. FLASHING
  - SHOE VENEER
  - 1" X 3 CEDAR BATTENS + 2" OC OVER 1/2" ACQ PLYWOOD
- THE TYPE OF EXTERIOR FINISH, THE INSTALLATION AND THE WATERPROOFING DETAILS ARE ALL TO BE THE FULL RESPONSIBILITY OF THE OWNER/BUILDER. THIS DESIGNER ASSUMES NO RESPONSIBILITY FOR THE INTEGRITY OF THE BLDG ENVELOPE



LEFT SIDE ELEVATION  
SCALE: 1/4" = 1'-0"



FRONT ELEVATION  
SCALE: 1/4" = 1'-0"

2018  
PROJECT MANAGER/ARCHITECT  
DRAWN: GENERAL LAW

**25# SNOW LOAD**


UPPER FLOOR	600 SQ. FT.
MAIN FLOOR	1700 SQ. FT.
<b>SUB-TOTAL</b>	<b>2300 SQ. FT.</b>
BONUS	+ 300 SQ. FT.
<b>GARAGE AREA</b>	<b>+ 400 SQ. FT.</b>

THE CONTRACTOR ASSUMES FULL RESPONSIBILITY FOR THE CORRECT INSTALLATION OF ALL EXTERIOR FINISHES AND WEATHERPROOFING.

COPYRIGHT © 2018


22201

1




RIGHT SIDE ELEVATION

SCALE: 1/4" = 1'-0"



1 POP-OUT DETAIL  
SCALE: 1/2" = 1'-0"



REAR ELEVATION

SCALE: 1/4" = 1'-0"

222201-02  
PROJECT MANAGER/AS  
DRAWN: CEN/PLD/LAV


- CHIMNEY TO EXTEND MIN 24" ABOVE ANY ROOF WITHIN 10' HORIZONTAL
- ROOFING MATERIAL (SEE ROOF PLAN)
- CEDAR SHINGLE SIDING INSTALL PER 1/4" INCH SPEC.
- 6" I GUTTER ON 2" X 8" RAFTER C/W DOWNSPOUTS (SEE ROOF PLAN)
- 5/4" X CEDAR CORNER EDS.
- 1" X 3" CEDAR BATTENS @ 24" O.C. OVER 1/2" ACP PLYWOOD

THE TYPE OF EXTERIOR FINISH, THE INSTALLATION AND THE WATERPROOFING DETAILS ARE ALL TO BE THE FULL RESPONSIBILITY OF THE OWNER/OWNER. THIS DESIGNER ASSUMES NO RESPONSIBILITY FOR THE INTEGRITY OF THE BLDG ENVELOPE

**25# SNOW LOAD**

UPPER FLOOR	600 SQ. FT.
MAIN FLOOR	1700 SQ. FT.
<b>SUB-TOTAL</b>	<b>2300 SQ. FT.</b>
BONUS	+ 300 SQ. FT.
GARAGE AREA	+ 400 SQ. FT.

22201  
2



- LEGEND**
- RECEIVED INCANDESCENT
  - RECEIVED DIRECTIONAL INCANDESCENT FIXTURE
  - HALL MOUNTED INCANDESCENT
  - SURFACE MOUNTED INCANDESCENT
  - SURFACE MOUNTED FLUORESCENT
  - RECEIVED EXHAUST FAN VENTED TO THE EXTERIOR
  - CASABLANCA TYPE CEILING FAN
  - DUPLEX OUTLET
  - CEILING MOUNTED DUPLEX OUTLET
  - 200V OUTLET
  - FLUSH FLOOR MOUNTED OUTLET (HONEY LUCK)
  - TELEPHONE OUTLET
  - DATA OUTLET
  - TELEVISION OUTLET
  - SPEAKER LOCATION
  - SMOKE / CO DETECTOR (SEE GENERAL NOTES FOR OTHER SPEC'S)
  - BEARING POINT LOCATION (PROVIDE SOLID BEARINGS - MIN. OF 1" BENEATH EACH LEG)
  - POINT LOAD FROM ABOVE
  - 4" x 4" POST FROM ROOF JWP, VALLEY OR RIDGE SOON TO BEARING POINT ON WALL BELOW (SLAB OF 4" ROOF VENT)
  - BEARING WALL SUPPORTING STRUCTURE ABOVE
  - 4" x 10" HOR. BEARING WALL INT. DOOR & OPENINGS W/ MIN. (2) 2" x 8" SUPPORT E.A. END (MIN)
  - DROPPED STRUCT. MEMBER BEARING WALL

**ENERGY ENVELOPE KEY**

WALL/PURCHASE INSULATION R-11

WALL/PURCHASE INSULATION R-11

(SEE SHEET 10 FOR INSULATION VALUES)

**CO. DET. LOCATION**

CARBON MONOXIDE ALARMS SHALL BE LOCATED IN EA. BEDROOM OR OTHER REAR OUTSIDE OF EA. BEDROOM DOOR AT EVERY FLOOR LEVEL IN BEDROOMS (SEE SHEET 10 FOR ADD. INFO)

**MAIN FLOOR PLAN**  
SCALE: 1/4" = 1'-0"

IF LATERAL ENGINEERING IS REQUIRED, REFER TO ENGINEERING SHEETS FOR LATERAL SPECIFICATIONS

**25# SNOW LOAD**

UPPER FLOOR	600 SQ. FT.
MAIN FLOOR	1700 SQ. FT.
<b>SUB-TOTAL</b>	<b>2300 SQ. FT.</b>
BONUS	1300 SQ. FT.
<b>GARAGE AREA</b>	<b>4400 SQ. FT.</b>

**22201**  
**3**



- LEGEND**
- RECESSED INCANDESCENT
  - RECESSED DIRECTIONAL INCANDESCENT FIXTURE
  - WALL MOUNTED INCANDESCENT
  - SURFACE MOUNTED INCANDESCENT
  - SURFACE MOUNTED FLUORESCENT
  - RECESSED EXHAUST FAN VENTED TO THE EXTERIOR
  - CASAMBLANCIA TYPE CEILING FAN
  - DUPLEX OUTLET
  - CEILING MOUNTED DUPLEX OUTLET
  - 200V OUTLET
  - FLUSH FLOOR MOUNTED OUTLET (VERIFY LOC.)
  - TELEPHONE OUTLET
  - DATA OUTLET
  - TELEVISION OUTLET
  - SPEAKER LOCATION
  - SMOKE / CO DETECTOR (SEE GENERAL NOTES FOR OTHER TYPES)
  - BEARING POINT LOCATION (PROVIDE BOLD BEARING MIN. OR MEMBER WIDTH (IND.))
  - POINT LOAD FROM ABOVE
  - 4 x 4 POST FROM ROOF HP. WALL OR RISER DOWN TO BEARING POINT ON WALL BELOW (MAX. OF 45" FROM VERT.)
  - BEARING WALL SUPPORTING STRUCTURE ABOVE
  - 4 x 12 HDR. BEARING WALL NT. DOOR & OPENINGS W/ MIN. (2) 2 x 4 SUPPORT EA END (IND.)
  - DROPPED STRUCT. MEMBER BEARING \* WALL

**ENERGY ENVELOPE KEY**

- WALL/FLOOR/CL. NSUL.
- FOUNDATION NSUL.
- (SEE SHEET 11 FOR INSULATION VALUES)

**C.O. DET LOCATION**

CARBON MONOXIDE ALARMS SHALL BE LOCATED IN EA. BEDROOM OR WITHIN 5 FEET OUTSIDE OF EA. BEDROOM DOOR AT EVERY FLOOR LEVEL W/ BEDROOMS (SEE SHEET 11 FOR ADD. INFO)



**TYPICAL FLASHINGS**  
1/4" = 1'-0"




**UPPER FLOOR PLAN**  
SCALE: 1/4" = 1'-0"

IF LATERAL ENGINEERING IS REQUIRED, REFER TO ENGINEERING SHEETS FOR LATERAL SPECIFICATIONS

25% INNOVATION PROJECT MANAGERS DRAWING BOARD LAW

**25% INNOVATION**

UPPER FLOOR	650 SQ. FT.
MAIN FLOOR	1750 SQ. FT.
<b>SUB-TOTAL</b>	<b>2400 SQ. FT.</b>
BONUS	+ 340 SQ. FT.
GARAGE AREA	+ 460 SQ. FT.



TYP. WALL SECTION  
SCALE: 3/4" = 1'-0"


**ROOFING MATERIAL**  
(SEE ROOF PLAN)  
3/8\"/>

**FLOOR FINISH**  
1/2\"/>

**FLOOR FINISH**  
1/2\"/>

**RECOMMENDED FOTM DIMS**  
(SEE GRADE) "A" "B" "C"  
1 STORY: 10' 0" 10' 0" 10' 0"  
2 STORY: 10' 0" 10' 0" 10' 0"  
3 STORY: 10' 0" 10' 0" 10' 0"  
3/8\"/>

\* SEE OPT. SHEET "A" FOR OTHER CONDITIONS THAT MAY APPLY.  
4" x PERFORATED DRAIN TILE (TYP. UNDER REVD)



FOUNDATION PLAN  
SCALE: 1/4" = 1'-0"


2025 03 14 11:58 AM  
PROJECT MANAGER  
DRAWN: GUY/LS/MS

**25# SNOW LOAD**


UPPER FLOOR	600 SQ. FT.
MAIN FLOOR	1700 SQ. FT.
<b>SUB-TOTAL</b>	<b>2300 SQ. FT.</b>
BONUS	+ 300 SQ. FT.
GARAGE AREA	+ 400 SQ. FT.

22201  
5 A


IF LATERAL ENGINEERING IS REQUIRED, REFER TO ENGINEERING SHEETS FOR LATERAL SPECIFICATIONS



**FIREPLACE SECTION**  
SCALE: 1/2" = 1'-0"



**B BUILDING SECTION**  
SCALE: 1/4" = 1'-0"



**D BUILDING SECTION**  
SCALE: 1/4" = 1'-0"

**URETHANE DECK SYSTEM**


**RECOMMENDATIONS**  
The deck sub structure has been designed to meet the load requirements as recommended by most waterproof deck coating manufacturers. Specific details, materials and methods are critical to the performance of the deck coating system. Therefore, determine the product to be applied and follow all installation recommendations. Proper taping is required to process the integrity of the deck and structure. It is strongly recommended that an installer expert is consulted regarding all aspects of preparation, installation and maintenance of the urethane deck system.

Reference for urethane deck consultant:  
Gold Dog Exteriors  
5149 SE 51st Ave.  
Portland, OR 97086  
(503) 761-7171 [www.GOLDDOGEXTERIORS.COM](http://www.GOLDDOGEXTERIORS.COM)

The following are typical mfr. recommendations for the purpose of estimating only. Consult mfr. specifications for actual product to be applied.

- 1. FLYWOOD GRADES**  
Flywood shall be AC Exterior Underlayment with plugged crossbands under the face meeting specifications of the American Plywood Association (APA) and carrying the grade trademark of the APA. Plywood shall conform to US Plywood Standards PS 1-183.
- 2. INSTALLATION**  
All panel edges shall be supported on 2" lumber blocking or pricing framing so as to ensure no unsupported edges. Taper and groove edging in panels less than 1-1/8" thick does not replace blocking and is unacceptable.  
Place plywood panels in moderate contact without forcing panels together (maximum 1/8" spacing). Taking special care not to damage the edges. Plywood shall be continuous across top of roof eave with face grain across supports and long dimension perpendicular to supports. Joints shall be level and smooth.


- Thickness of plywood and seams shall meet following minimums except where local building codes require greater thickness:
- 3. 3/4"** for supports up to 24" o.c.
  - (1/2)"** can be used over solid substrates but must be installed with no joints coinciding with joints in the substrate.
  - 3. SLOPE**  
The deck shall be sloped a minimum of 1/4" to the foot and constructed as to drain freely, preferably to a drain or gutter. Gasketed coatings cannot be used to provide such slopes.
  - 4. VENTILATION**  
Gastroflex coatings provide an effective vapor retarder. Good design requires that adequate ventilation be provided for all spaces enclosed.
  - 5. NAILING**  
Use non-rusting screws with countersunk heads, hot-dipped galvanized (rough 8000) or stainless steel with only Space Fasteners 6" o.c. along panel edges and 12" o.c. along intermediate supports. Space 12" o.c. in all directions when installing 1/2" on solid substrates. See fasteners flush without fastening the plywood. Adaptive nailing which indents the surface shall not be used.
  - 6. PROTECTION**  
The plywood shall be protected by the plywood installer prior to application of the coating. It shall be turned over to the applicator clean, dry and free from paint, plaster, asphalt, oil, dirt or other surface contaminants.




**ENERGY ENVELOPE KEY**

(Symbol: Dashed lines)	WALL/FLR/GI. NAIL
(Symbol: Solid lines)	FOUNDATION NAIL
(Symbol: Dotted lines)	(SEE SHEET 'G' FOR INSULATION VALUES)


**WATERPROOF DECK ASSEMBLY**  
SCALE: NONE = 1'-0"



**C BUILDING SECTION**  
SCALE: 1/4" = 1'-0"



**B BUILDING SECTION**  
SCALE: 1/4" = 1'-0"



**A BUILDING SECTION**  
SCALE: 1/4" = 1'-0"

2020-10-10  
PROJECT MANAGER: AD  
DRAWN: CHEN/MS/LAW

**25# SNOW LOAD**

UPPER FLOOR	600 LB. SQ. FT.
MAIN FLOOR	150 LB. SQ. FT.
BURT TOTAL	2300 LB. SQ. FT.
BONUS	+ 300 LB. SQ. FT.
GARAGE AREA	+ 400 LB. SQ. FT.

**22201**  
**6**







**RADON MITIGATION**

THE FOLLOWING CONSTRUCTION TECHNIQUES AND MEASURES ARE INTENDED TO MITIGATE RADON ENTRY IN NEW CONSTRUCTION. THESE TECHNIQUES MAY BE REQUIRED BY A JURISDICTION OR JURISDICTIONS BASED ON EXISTING AS OF APRIL 1, 2011, IN THE STATE OF OREGON. THE COUNTIES OF MULTNOMAH, WASHINGTON, CLATSOP, CLATSOP, MULTNOMAH, WASHINGTON AND BAKER REQUIRE RADON MITIGATION FOLLOWING THE U.S. EPA MODEL STANDARDS AND TECHNIQUES FOR CONTROL OF RADON IN NEW RESIDENTIAL BUILDINGS. THESE SPECIFICATIONS MEET MOST NATIONAL CODES. THE BUILDER AND HOME OWNER SHOULD CHECK FOR ANY LOCAL VARIANTS TO THESE GUIDELINES.

**BUILDING TIGHTNESS MEASURES**

THE FOLLOWING ARE POINTS OF ENTRY TO PROTECT FROM PASSAGE OF RADON GAS INTO LIVING SPACE. PROVIDE NON-PENETRATING GASKET OR EQUIVALENT SEALANT AT THE FOLLOWING CRITICAL POINTS:

**SLAB ON-GRADE AND BASEMENT WALLS**

- CRACKS IN CONCRETE SLABS
- COLD JOINT BETWEEN TWO CONCRETE POURS
- POLES AND JOINTS IN CONCRETE BLOCK
- FLOOR TO WALL CRACK OR FINISH DRAIN
- EXPOSED SOIL AS IN A SUMP
- SEWING DRAIN TILE, P DRAINAGE TO OPEN BUMP
- MORTAR JOINTS
- LOOSE-FITTING PIPE PENETRATIONS
- OPEN TOPS OF BLOCK WALLS
- WATER FROM ROOF BELLS
- UNTRAPPED FLOOR DRAIN TO A DRY WELL OR SEPTIC SYSTEM

**CRAIL SPACE**

- CRACKS IN SUBFLOORING AND FLOORING
- SPACES BEHIND STUD WALLS AND BRICK VENEER WALLS THAT REST ON UNCOMPLETED FLOOR-BLOCK FOUNDATION
- ELECTRICAL PENETRATIONS
- LOOSE-FITTING PIPE PENETRATIONS
- OPEN TOPS OF BLOCK WALLS
- WATER FROM ROOF BELLS
- HEATING DUCT REGISTER PENETRATIONS
- COLD-AIR RETURN DUCTS IN CRAIL SPACE

COORDINATE DRAINS SHALL BE RUN TO THE EXTERIOR USING NON PERFORATED PIPE OR SHALL BE PROVIDED WITH AN APPROVED TRAP.

SUMP PITS THAT SERVE AS END POINT FOR A SUB-SLAB OR EXTERIOR DRAIN TILE LOOP SYSTEM AND SUMP PITS WHICH ARE NOT BUILT FROM THE SOIL SHALL BE FITTED WITH A GASKETED OR SEALED. IF THESE THE SUMP IS USED AS THE SUCTION POINT IN A SUB-SLAB DEPRESSURIZATION SYSTEM THE LID MUST BE DESIGNED TO ACCOMMODATE THE SUMP BEING USED AS A FLOOR DRAINING. THE SUMP PIT LID SHALL HAVE A TRAPPED ALLET.

DUCTWORK WHICH PASSES THROUGH OR BENEATH A CONCRETE FLOOR SLAB SHALL BE FREE OF SEAMS AND MUST BE PERFORMANCE TESTED. DUCTWORK PASSING THROUGH A CRAILSPACE MUST HAVE ALL SEAMS AND JOINTS SEALED (PER PARAGRAPH 1). ALL JOINTS OF DUCT SYSTEMS USED IN THE HEATING OR COOLING OF A CONDITIONED SPACE SHALL BE SEALED BY MEANS OF TAPERS, MASTIC, ABSORBENT SEALANT, GASKETING OR OTHER APPROVED CLOSURE SYSTEMS. WHERE MASTIC IS USED TO SEAL OPENINGS GREATER THAN 1/4", A COMBINATION OF MASTIC AND TAPER SHALL BE USED.

CRAILSPACE ACCESS OR UNDER-FLOOR MECHANICAL EQUIPMENT ACCESS, OR ANY OTHER ACCESS POINT FROM THE HABITABLE SPACE INTO THE CRAIL SPACE, SUCH AS DOORS OR PANELS, MUST BE CLOSED AND GASKETED TO CREATE AN AIRTIGHT SEPARATION.

AIR HANDLING UNITS IN CRAIL SPACES SHALL BE SEALED TO PREVENT AIR FROM BEING DRAWN INTO THE UNIT.

**CRAIL SPACE RADON MITIGATION**

IN ADDITION TO THE CRAIL SPACE SEALING REQUIREMENTS, ONE OF THREE RADON MITIGATION METHODS SHALL BE IMPLEMENTED:

METHOD 1 - MECHANICAL VENTILATION (VARIABLE EXHAUSTION)

- PROVIDE AN APPROVED MECHANICAL CRAIL SPACE VENTILATION SYSTEM OR OTHER EQUIVALENT SYSTEM.

METHOD 2 - PASSIVE SUB-MEMBRANE DEPRESSURIZATION SYSTEM (SUMP)

- PROVIDE FOUNDATION VENTILATION SYSTEM (SEE FOUNDATION NOTES FOR CRAILSPACE VENTING)
- PROVIDE A SOIL GAS RETARDER SUCH AS 6-ML POLYETHYLENE OR EQUIVALENT (SEE GAS-RETARDER NOTES)
- PROVIDE A VENT STACK (SEE VENT STACK NOTES)

METHOD 3 - CRAILSPACE VENTILATION AND BUILDING TIGHTNESS

- PROVIDE NO LESS THAN ONE NET SQ FT OF CRAILSPACE FOUNDATION VENT AREA PER EACH SQ FT OF FLOOR FLOOR AREA (SEE FOUNDATION NOTES FOR CRAILSPACE VENTING LOCATION REQUIREMENTS)
- OPERABLE LOUVERS, DAMPERS, OR OTHER MEANS TO TEMPORARILY CLOSE OFF VENT OPENINGS NOT ALLOWED TO FEEL THE REQUIREMENTS OF THIS RADON MITIGATION METHOD.
- DUCTS SHALL BE TESTED WITH A SMOKE PUFF OR DEPRESSURE TESTING TO 50 PASCALS FROM AMBIENT CONDITIONS AND ROAD TO DETERMINE MORE THAN 1% AIR CHANGES PER HOUR.
- INSTALL A MECHANICAL EXHAUST SUPPLY, OR COMBINATION VENTILATION SYSTEM PROVIDING MAKE-BUILDING VENTILATION RATES AS PER TABLE 100.3.

**VENTILATION AIR REQUIREMENTS (cfm)**

FLOOR AREA (sq ft)	NUMBER OF BEDROOMS			
	0-1	2-3	4-5	>1
<3500	50	45	40	35
3500-4500	45	40	35	30
4500-5500	40	35	30	25
5500-6500	35	30	25	20
6500-7500	30	25	20	15
>7500	25	20	15	10

**SLAB-ON-GRADE/BASEMENT RADON MITIGATION**

A PASSIVE SUB-SLAB DEPRESSURIZATION SYSTEM SHALL BE INSTALLED DURING CONSTRUCTION IN BASEMENT OR SLAB-ON-GRADE BUILDINGS. FOLLOWING NOTES DESCRIBE REQUIRED BUILDING TIGHTNESS MEASURES AND ASSEMBLE THE FOLLOWING ELEMENTS OF THE MITIGATION SYSTEM:

- PROVIDE A RADON VENT PIPE EXTENDING FROM A GAS PERMEABLE LAYER BENEATH THE SLAB FLOOR SYSTEM THROUGH THE FLOOR OF THE DWELLING AND TERMINATING AT THE ROOF.
- SEAL INTER PENETRATING VENT PIPE, SOIL-GAS-RETARDER AND SLAB REINFORCER PREPARATION.

**SLAB SUB-FLOOR PREPARATION**

- A LAYER OF GAS-PERMEABLE MATERIAL SHALL BE PLACED UNDER ALL CONCRETE SLABS AND OTHER FLOOR SYSTEMS THAT DIRECTLY CONTACT THE GROUND, AND ARE WITHIN THE WALLS OF THE LIVING SPACES OF THE BUILDING. THE GAS-PERMEABLE LAYER SHALL CONSIST OF ONE OF THE FOLLOWING:

1. A UNIFORM LAYER OF CLEAN AGGREGATE, A MINIMUM OF 4 INCHES THICK, THE AGGREGATE SHALL CONSIST OF MATERIAL SMALL ENOUGH TO PASS THROUGH A 2" SIEVE AND BE RETAINED BY A 1/4" SIEVE.
2. A UNIFORM LAYER OF SAND, NATIVE OR FILL, A MINIMUM OF 4 INCHES THICK, OVERLAIN BY A LAYER OF STRIPS OF GEO-TEXTILE DRAINAGE MATTING DESIGNED TO ALLOW THE LATERAL FLOW OF SOIL GASES.

**SOIL-GAS-RETARDER**

- THE SOIL GASES RETARDER SHALL BE COVERED WITH A CONTINUOUS LAYER OF 1/4" MIN. 6-ML POLYETHYLENE SOIL-GAS-RETARDER. THE GROUND COVERING SHALL BE LIMITED A MINIMUM OF 2 INCHES AT JOINTS AND SHALL EXTEND TO ALL FOUNDATION WALLS INCLUDING THE CRAIL SPACE AREA.
- THE SHEETING SHALL FIT CLOSELY AROUND ANY PIPE OR OTHER PENETRATIONS OF THE MATERIAL.
- ALL FRANCHURES OR TEAMS IN THE MATERIAL SHALL BE SEALED OR COVERED WITH ADDITIONAL SHEETING.

**VENT PIPE (RADON)**

- A FLUSHING TEE OR OTHER APPROVED CONNECTION SHALL BE INSTALLED HORIZONTALLY BENEATH THE SOIL-GAS-RETARDER SHEETING AND CONNECTED TO A 3" OR 4" DIAMETER FITTINGS WITH A CRITICAL VENT PIPE INSTALLED THROUGH THE SHEETING.
- THE VENT PIPE SHALL BE EXTENDED UP THROUGH THE BUILDING FLOOR TO TERMINATE AT LEAST 3 INCHES ABOVE THE ROOF SURFACE IN A LOCATION AT LEAST 10 FEET AWAY FROM ANY WINDOW OR OTHER OPENING INTO THE CONDITIONED SPACES OF THE BUILDING THAT IS LESS THAN 1 FEET BELOW THE EXHAUST POINT, AND 10 FEET FROM ANY WINDOW OR OTHER OPENING IN A DOWNWIND ADJACENT BUILDING.
- IN BUILDINGS WHERE INTERIOR ROOFINGS OR OTHER BARRIERS SEPARATE THE SUB-SLAB AGGREGATE OR OTHER GAS-PERMEABLE MATERIAL, EACH AREA SHALL BE FITTED WITH AN INDIVIDUAL VENT PIPE.
- MULTIPLE VENT PIPES SHALL CONNECT TO A SINGLE VENT THAT TERMINATES ABOVE THE ROOF ON EACH INDIVIDUAL VENT PIPE SHALL TERMINATE ABOVE THE ROOF.
- ALL COMPONENTS OF THE RADON VENT PIPE SYSTEM SHALL BE INSTALLED TO PROVIDE POSITIVE DRAINAGE TO THE GROUND.
- RADON VENT PIPES SHALL BE ACCESSIBLE FOR INSURE FAN INSTALLATION THROUGH AN ATTIC OR OTHER ACCESS TO THE HABITABLE SPACE OR AN APPROVED ROOF TOP ELECTRICAL SUPPLY FAN.
- ALL EXPOSED AND VISIBLE INTERIOR RADON VENT PIPES SHALL BE IDENTIFIED WITH AT LEAST ONE LABEL ON EACH FLOOR AND AN ACCESSIBLE ATTIC. THE LABEL SHALL READ: "RADON REDUCTION SYSTEM".

**POWER SOURCE REQUIREMENT**

TO ACCOMMODATE NOTICE INSTALLATION OF AN ACTIVE SUB-MEMBRANE OR SUB-SLAB DEPRESSURIZATION SYSTEM, AN ELECTRICAL CIRCUIT TERMINATED IN AN ATTIC OR OTHER ANTICIPATED LOCATION OF VENT PIPE FAN ELECTRICAL SUPPLY SHALL ALSO BE ACCESSIBLE IN ANTICIPATED LOCATION OF SYSTEM FAILURE ALARMS.


**COMBINATION FOUNDATIONS**

COMBINATION BASEMENT/CRAIL SPACE OR SLAB-ON-GRADE/CRAIL SPACE FOUNDATIONS SHALL HAVE SEPARATE RADON MITIGATION SYSTEMS IN EACH TYPE OF FOUNDATION. A PASSIVE SUB-SLAB AND PASSIVE SUB-MEMBRANE RADON VENT PIPES MAY BE CONNECTED TO A SINGLE VENT TERMINATING ABOVE THE ROOF OR EACH VENT MAY INDIVIDUALLY COME TO TERMINATE ABOVE THE ROOF (SEE VENT PIPE NOTES).

**PASSIVE SUB-SLAB DEPRESSURIZATION RADON CONTROL SYSTEM FOR NEW CONSTRUCTION**

**NOTES:**

1. ALL CONCRETE SLABS THAT COME IN CONTACT WITH THE GROUND SHALL BE LAD OVER A GAS PERMEABLE MATERIAL, MADE UP OF EITHER A MINIMUM 4" THICK LAYER OF CLEAN AGGREGATE, OR A MINIMUM 4" THICK UNIFORM LAYER OF SAND OVERLAIN BY A LAYER OF STRIPS OF MANUFACTURED MATTING DESIGNED TO ALLOW THE LATERAL FLOW OF SOIL GASES.
2. ALL CONCRETE FLOOR SLABS SHALL BE DEMOLISHED AND RECONSTRUCTED IN ACCORDANCE WITH LOCAL BUILDING CODES. ADDITIONAL REFER: AMERICAN CONCRETE INSTITUTE PUBLICATIONS, "ACI 308R-14" AND "ACI 308R-14" FOR THE MOST RECENT REVISIONS. DESIGN AND CONSTRUCTION OF POST-TENSIONED SLABS ON GROUND.
3. ALL OPENING GAPS AND JOINTS IN FLOOR AND WALL ASSEMBLIES IN CONTACT SOIL OR GROUND AROUND TOILETS, BATHTUBS OR DRAINS PENETRATING THESE ASSEMBLIES SHALL BE FILLED OR CLOSED WITH MATERIALS THAT PROVIDE A PERMANENT AIR-TIGHT SEAL. SEAL LARGE OPENINGS WITH NON-SHRINK MORTAR, GROUTS OR EXPANDING FOAM MATERIALS AND SMALLER GAPS WITH AN ELASTOMERIC JOINT SEALANT, AS DEFINED IN ASTM C828-01.
4. VENT PIPES SHALL BE INSTALLED SO THAT ANY RAINWATER OR CONDENSATION DRAINS DOWNWARD INTO THE GROUND BENEATH THE SLAB OR SOIL-GAS-RETARDER MEMBRANE.
5. CIRCUITS SHOULD BE A MINIMUM 2 AMP, 15 VOLT.




**SLAB ON-GRADE/BELOW-GRADE (BASEMENTS) SUB-MEMBRANE DEPRESSURIZATION SYSTEM**

**PASSIVE RADON CONTROL SYSTEM IN CRAIL SPACE FOR NEW CONSTRUCTION**

**NOTES:**

1. INSTALL A LENGTH OF 3" OR 4" DIAMETER PERFORATED DRAIN TILE HORIZONTALLY BENEATH THE SHEETING AND CONNECT TO THE FITTING WITH THE VERTICAL STANDPIPE THROUGH THE SOIL-GAS-RETARDER MATERIAL. THIS HORIZONTAL PIPE SHOULD NORMALLY BE PLACED PARALLEL TO THE LONG DIMENSION OF THE HOME AND SHOULD EXTEND NO CLOSER THAN 6 FEET TO THE FOUNDATION WALL.
2. VENTILATE CRAILSPACES IN CONFORMANCE WITH LOCAL CODES. VENTS SHALL BE OPEN TO THE EXTERIOR AND BE OF NON-COMBUSTIBLE DESIGN.
3. CIRCUITS SHOULD BE A MINIMUM 2 AMP, 15 VOLT.



**CRAILSPACE SUB-MEMBRANE DEPRESSURIZATION SYSTEM**

2020-11-18 PROJECT MANAGER'S DRAWING: 22201-1-10

**25# SNOW LOAD**

UPPER FLOOR	50# SQ. FT.
MAIN FLOOR	150# SQ. FT.
BASE TOTAL	200# SQ. FT.
BONUS	0# SQ. FT.
GARAGE AREA	0# SQ. FT.

**22201**  
**R**